### TULSA METROPOLITAN AREA PLANNING COMMISSION

INCOG - 2 West 2nd Street, Suite 800 - Tulsa, Oklahoma 74103 - (918) 584-7526 - FAX (918) 583-1024

tulsaplanning.org

[ ] SUBDIVISION PLAT [ ] MINOR SUBDIVISION PLAT				
APPLICATION INFORMATION				
RECEIVED BY: DATE FILED:	PLAT N	NAME: JACK WILLS		
[X] CITY [ ] COUNTY REF				
SUBDIVISION PLAT SCHEDULE		REFERENCE CASES		
PUBLIC AGENCY REVIEW:		ZONING/PUD/CO CASE:		
		TMAPC DATE:		
TMAPC:		BOA CASE:		
		BOA DATE:		
SUBJECT PROPERTY INFOR	MATION			
ADDRESS OR DESCRIPTIVE LOCATI	ON: 6414 S 105th F AVE	NUE 1		
LEGAL DESCRIPTION: LOTS 5 & 6			10101012L. 4.00 1 acics	
LEGAL DESCRIPTION: LOTO GAR	DECORTO, CITION CAND	ZENO ABBITION	*	
	CO-2	6-18N-1/F	<b>7</b>	
		T-R-S: 6-18N-14E COUNCIL DISTRICT: 1		
		SANITARY SEWER: CITY OF TULSA		
		V: COX SCHOOL DISTRICT:	1-9A	
INFORMATION ABOUT YOUR	PROPOSAL			
PROPOSED ZONING: C0-2		:1	DPOSED: 1	
		PROPERTY OWNER INFORMA		
APPLICANT INFORMATION  NAME John Droz		NAME Jack H Wills, III		
ADDRESS 28 N Water Street		ADDRESS 5891 S Garnett Rd		
CITY, ST, ZIP Sapulpa, OK 74066		CITY, ST, ZIP Tulsa, OK, 74146		
DAYTIME PHONE 918-520-9976		DAYTIME PHONE 918-949-8948		
EMAIL john@66eng.com		EMAIL jwills@jackwills.net		
I, THE UNDERSIGNED APPLICANT, CERTIFY THAT THE INFORMATION ON THIS APPLICATION IS TRUE AND CORRECT.				
SIGNATURE & DATE:				
DOES OWNER CONSENT TO THIS AI	PPLICATION [ ] YES [ ] NO			
WHAT IS APPLICANT'S RELATIONSH	IP TO OWNER?			
APPLICATION FEES (Make che	ecks pavable to INCOG)	PRELIMINARY PLAT DISPOSIT	TION	
PRELIMINARY PLAT <b>FEE</b> :	\$1,200	TMAPC ACTION: [ ] APPROVED [ ] DE	NIED	
FINAL PLAT <b>FEE</b> :	\$900	DATE/VOTE:		
<u> </u>		CONDITIONS:		
TOTAL AMOUNT DUE: \$ 1200				
RECEIPT NUMBER:				
APPLICATION F	EES IN WHOLE OR PART WILL NOT	T BE REFUNDED AFTER NOTIFICATION HAS BEE	N GIVEN.	

### **SUBMITTAL REQUIREMENTS:**

Checklists for all submittals are available at tulsaplanning.org.

Preliminary Plats - Application, Checklist, 4 folded full-size copies & PDF of plat, deed of dedication, and Conceptual Improvement Plan

Draft Final Plats - 4 folded full-size copies & PDF

Final Plats for Signatures - 8-10 rolled full-size copies, fully executed by owner, surveyor, and engineer

INCOG - 2 West 2nd Street, Suite 800 - Tulsa, Oklahoma 74103 - (918) 584-7526 - FAX (918) 583-1024

### SUBDIVISION PRE-APPLICATION REVIEW

PROJECT INFORMATION			
Subdivision Location: West of S.105TH E Ave. and East of 103RD E. Ave.			
Acreage: 4.59 Number of Lots: 1 Project Name: Jack Wills			
Owner of Property: JWJR, LLC.			
Person Requesting Review: John Droz Date:			
COMPREHENSIVE PLAN STATUS			
LAND USE DESIGNATION: Regional Center GROWTH OR STABILITY DESIGNATION: Area of GFrowth			
The property [ ] CONFORMS [ ] DOES NOT CONFORM to the Major Street and Highway Plan.			
ZONING AND PLATTING			
The property is currently zoned CO-2			
The proposed use of			
Minimum lot size required:  4.59 acres			
Is the property is located within an approved development plan? [x] YES [ ] NO			
If yes, does the project conform to all development standards? [X] YES [ ] NO			
Is there a Rezoning or Board of Adjustment case pending on the site? [X] YES [ ] NO Case number:			
When are the anticipated TMAPC and City Council, or Board of Adjustment meeting dates?			
INFRASTRUCTURE NEEDS			
A brief summary of major infrastructure to be provided and by whom:  StreetsN/A			
Water Water line provided by developer			
Sewer Private utilities provided by developer			
Storm Water/Drainage Detention and storm pipes provided by developer			
Park and Trail Dedications N/A			

### Please consider the items in this Pre-Application Review carefully.

This conceptual pre-development review is not intended to be all-inclusive, but rather to address the major development criteria, which should be thoroughly studied as development plans progress. Relevant Federal and State Statutes, as well as TMAPC Subdivision Regulations, Design Criteria, Zoning Codes, and other relevant local codes and policies should be reviewed and incorporated into future plans.

Please contact the Subdivision Coordinator at any time at 584-7526 if you have questions about the development process in the Tulsa Metropolitan Area.

### TULSA METROPOLITAN AREA PLANNING COMMISSION

INCOG - 2 West 2nd Street, Suite 800 - Tulsa, Oklahoma 74103 - (918) 584-7526 - FAX (918) 583-1024

tulsaplanning.org

### SUBDIVISION PLAT PROCESS

MEETING COLLEDING

WILL I ING SCIILDOLL	
Public Agency Review (PAR) Date (Preliminary plats): Thursday,	1:30 p.m.
Large Conference Room, 8th Floor, INCOG, 2 West 2nd Street	
Tulsa Metropolitan Area Planning Commission (TMAPC) Date (Preliminary plats): We	dnesday,1:30 p.r
Tulsa City Council Room, 2nd Level, One Technology Center, 175 East 2nd Street	

### PRELIMINARY PLAT PROCESS

- Applicant submits preliminary plat/covenants, conceptual improvements plan, completed application, and fees. Plat is scheduled for PAR
  meeting and TMAPC public hearing.
- 2. Staff distributes preliminary plat to PAR members for review.
- 3. Applicant, staff, and PAR members meet to review requirements for approval of preliminary plat.
- 4. TMAPC holds public hearing to consider approval of preliminary plat. Approval of a preliminary plat expires after one year.

### FINAL PLAT PROCESS

- 1. Applicant prepares "draft final" plat in accordance with all TMAPC and PAR requirements of preliminary plat approval. Staff will review and stamp "Draft Final" and digitally stamp "Draft Final" PDF submittal.
- 2. If revisions are made after the first "draft final" plat submittal, new plats shall be submitted and clearly identify all revisions on the face of the plat and in the covenants by either clouding or shading. There shall be a clear identifying mark (usually a small triangle) containing a revision number attached to each clouded or shaded item and a table of revision numbers and revision dates. In addition, a brief description of the nature of the revision should be included in the table.
- 3. Applicant distributes "draft final" for release as follows: 1 copy TMAPC staff; 2 copies Development Services; PDF Utility Providers
- 4. Release letters are required from the following: City of Tulsa Development Services OR County Engineer, water and sanitary sewer service providers; City Legal Department (if property is within the city limits of Tulsa); electric, gas, telephone and TV utility service providers. Release letters shall indicate the latest revision date for which the plat is being released.
- 5. Revisions submitted subsequent to being released shall be reviewed and released again. TMAPC staff must have the latest final plat incorporating all of the revisions before placing on the agenda for approval by the Planning Commission.
- 6. Staff will schedule "draft final" plat for TMAPC approval after we receive all release letters and have confirmed that the release letters pertain to the latest revised version of the plat. Submittals required per Section 3.6.5 of the Subdivision Regulations must be received before the Final Plat is considered by TMAPC.
- 7. TMAPC considers approval of final plat.
- 8. Applicant submits final recordable documents with original notarized signatures to TMAPC staff.
- 9. Staff obtains signatures from TMAPC, City Attorney, City Engineering, Mayor and City Council for plats in City of Tulsa. For plats in unincorporated Tulsa County, staff obtains signatures from TMAPC and County Engineer.
- 10. Staff returns final signed documents to applicant for filing with the County Clerk. Final documents must be filed within one year of TMAPC final plat approval. One filed paper copy and the 2 required electronic discs are delivered to staff.


### PRELIMINARY PLAT JACK WILLS

A SUBDIVISION IN THE CITY OF TULSA, TULSA COUNTY, OKLAHOMA, BEING A PART OF THE SE/4 OF THE NW/4 OF SECTION SIX (6), TOWNSHIP 18 NORTH, RANGE 14 EAST OF THE INDIAN BASE AND MERIDIAN.

# UNION GARDENS CENTRAL PARK AT UNION NEWHART-HUTSON MICHAEL TERRACE RESUB SITE MICHAEL TERRACE AS S S REE | SOU H TACO BUENO NEAL PLAY SOUTH PORT TERRACE TERRACE ASBURY UNITED METHODIST CHURCH ASBURY UNITED METHODIST CHURCH TO SUGARBERRY AMENDED TO SUGARBERRY TO SUG

Location Map

SCALE: 1"=2000'



### OWNER / DEVELOPER

JWJR, LLC JACK H WILLS, III 8411 E. 41st TULSA, OK 74145 PH (901) 663-3370

### SURVEYOR

WALLACE DESIGN COLLECTIVE

123 NORTH MARTIN

LUTHER KING JR. BLVD.

TULSA, OKLAHOMA 74103


PH (918) 584-5858

E-mail: cliff.bennett@wallace.design

CA No. 1460 Renewal: June 30, 2025

### **ENGINEER**

ROUTE 66 ENGINEERING, LLC
28 NORTH WATER STREET
SAPULPA, OK 74066
PH (918) 248-1129
E-mail: bcox@66eng.com
CA No. 8853 Renewal: June 30, 2023



PROJECT JACK WILLS

Sheet 1 of 2

PRELIMINARY PLAT -AUGUST 07, 2023

### BENCHMARK

Benchmark
3/8" IRON PIN
ELEV.=705.88
N=396448.01
E=2600252.07
Benchmark
3/8" IRON PIN
ELEV.=701.11
N=396384.12
E=2600905.92

### **ADDRESSES**

ADDRESSES SHOWN ON THIS PLAT ARE ACCURATE AT THE TIME THE PLAT WAS FILED. ADDRESSES ARE SUBJECT TO CHANGE AND SHOULD NEVER BE RELIED ON IN PLACE OF THE LEGAL DESCRIPTION.

ACC. = LIMITS OF ACCESS
LNA = LIMITS OF NO ACCESS
RW/E = RESTRICTED WATERLINE

U/E = UTILITY EASEMENT

B/L = BUILDING SETBACK LINE

R/W = RIGHT-OF-WAY

SF = SQUARE FEET

**EASEMENT** 

SUBDIVISION CONTAINS 1 LOT IN 1 BLOCK

SUBDIVISION CONTAINS 4.56 TOTAL ACRES

THIS PLAT MEETS THE OKLAHOMA MINIMUM STANDARDS FOR THE PRACTICE OF LAND SURVEYING AS ADOPTED BY THE OKLAHOMA STATE BOARD OF LICENSURE FOR PROFESSIONAL ENGINEERS AND LAND SURVEYORS.


### LEGAL DESCRIPTION

LOTS FIVE (5) AND SIX (6), BLOCK SIX (6), UNION GARDENS, A SUBDIVISION IN TULSA COUNTY, STATE OF OKLAHOMA, ACCORDING TO THE RECORDED PLAT THEREOF.

CONTAINS 1 LOT, 1 BLOCK 4.59 ACRES, MORE OR LESS.

### BASIS OF BEARING

HORIZONTAL DATUM BASED UPON NAD 83 (1993) OKLAHOMA STATE PLANE COORDINATE SYSTEM NORTH ZONE 3501. VERTICAL DATUM BASED UPON NAVD 88.



### PRELIMINARY PLAT JACK WILLS

A SUBDIVISION IN THE CITY OF TULSA, TULSA COUNTY, OKLAHOMA, BEING A PART OF THE SE/4 OF THE NW/4 OF SECTION SIX (6), TOWNSHIP 18 NORTH, RANGE 14 EAST OF THE INDIAN BASE AND MERIDIAN.

### DEED OF DEDICATION AND DECLARATION OF RESTRICTIVE COVENANTS

### KNOW ALL MEN BY THESE PRESENTS:

JRWJR, LLC, HEREINAFTER REFERRED TO AS THE "OWNER/DEVELOPER", IS THE OWNER OF THE FOLLOWING DESCRIBED LAND IN THE CITY OF TULSA, TULSA COUNTY, STATE OF OKLAHOMA, TO-WIT:

LOTS FIVE (5) AND SIX (6), BLOCK SIX (6), UNION GARDENS, A SUBDIVISION IN TULSA COUNTY, STATE OF OKLAHOMA, ACCORDING TO THE RECORDED PLAT THEREOF.

### SECTION I. STREETS, EASEMENTS AND UTILITIES

### 1. PUBLIC STREETS AND UTILITY EASEMENTS

1.1. THE OWNER HEREBY DEDICATES TO THE PUBLIC THE UTILITY EASEMENTS DESIGNATED AS " U/EOR " UTILITYEASEMENT" FOR THE SEVERAL PURPOSES OF CONSTRUCTING, MAINTAINING, OPERATING, REPAIRING, REPLACING, AND/OR REMOVING ANY AND ALL PUBLIC UTILITIES, INCLUDING STORM SEWERS, SANITARY SEWERS, TELEPHONE AND COMMUNICATION LINES, ELECTRIC POWER LINES AND TRANSFORMERS, GAS LINES, WATER LINES AND CABLE TELEVISION LINES, TOGETHER WITH ALL FITTINGS, INCLUDING THE POLES, WIRES, CONDUITS, PIPES, VALVES, METERS, MANHOLES AND EQUIPMENT FOR EACH OF SUCH FACILITIES AND ANY OTHER APPURTENANCES THERETO, WITH THE RIGHTS OF INGRESS AND EGRESS TO AND UPON THE UTILITY EASEMENTS FOR THE USES AND PURPOSES STATED. PROVIDED THE OWNER RESERVES THE RIGHT TO CONSTRUCT, MAINTAIN, OPERATE, LAY AND REPAIR OR REPLACE WATER LINES AND SEWER LINES, TOGETHER WITH THE RIGHT OF INGRESS AND EGRESS FOR SUCH CONSTRUCTION, MAINTENANCE, OPERATION, LAYING, REPAIRING AND RE-LAYING OVER, ACROSS AND ALONG ALL OF THE UTILITY EASEMENTS DEPICTED ON THE PLAT, FOR THE PURPOSE OF FURNISHING WATER AND/OR SEWER SERVICES TO AREAS DEPICTED ON THE PLAT. THE OWNER HEREIN IMPOSES A RESTRICTIVE COVENANT, WHICH COVENANT SHALL BE BINDING ON EACH LOT OWNER AND SHALL BE ENFORCEABLE BY THE CITY OF TULSA, OKLAHOMA, AND BY THE SUPPLIER OF ANY AFFECTED UTILITY SERVICE, THAT WITHIN THE UTILITY EASEMENTS DEPICTED ON THE ACCOMPANYING PLAT NO BUILDING, STRUCTURE OR OTHER ABOVE OR BELOW GROUND OBSTRUCTION THAT INTERFERES WITH STATED USES AND PURPOSES OF THE UTILITY EASEMENTS SHALL BE PLACED, ERECTED, INSTALLED OR MAINTAINED, PROVIDED NOTHING HEREIN SHALL BE DEEMED TO PROHIBIT DRIVES, PARKING AREAS, CURBING, LANDSCAPING AND CUSTOMARY SCREENING FENCES THAT DO NOT CONSTITUTE AN OBSTRUCTION.

### 2. RESTRICTED WATERLINE EASEMENTS

2.1. THE OWNER DOES HEREBY DEDICATE TO THE PUBLIC PERPETUAL EASEMENTS ON, OVER, AND ACROSS THOSE AREAS DEPICTED ON THE ACCOMPANYING PLAT AS "RESTRICTEDWATERLINE EASEMENT" FOR THE PURPOSES OF CONSTRUCTING, MAINTAINING, OPERATING, REPAIRING, REPLACING, AND/OR REMOVING WATERLINES TOGETHER WITH ALL FITTINGS INCLUDING THE PIPES, VALVES, METERS AND EQUIPMENT AND OTHER APPURTENANCES THERETO TOGETHER WITH RIGHTS OF INGRESS AND EGRESS TO AND UPON THE EASEMENTS FOR THE USES AND PURPOSES STATED.

### 3. STORMWATER DETENTION EASEMENTS

- 3.1. THE OWNER DOES HEREBY DEDICATE TO THE PUBLIC PERPETUAL EASEMENTS ON, OVER, AND ACROSS THE PROPERTY DESIGNATED AND SHOWN ON THE ACCOMPANYING PLAT AS "STORMWATER DETENTION EASEMENT" FOR THE PURPOSES OF PERMITTING THE FLOW, CONVEYANCE, RETENTION, DETENTION AND DISCHARGE OF STORMWATER RUNOFF FROM THE SUBDIVISION.
- 3.2. DETENTION, RETENTION AND OTHER DRAINAGE FACILITIES LOCATED WITHIN THE STORMWATER DETENTION EASEMENTS SHALL BE CONSTRUCTED IN ACCORDANCE WITH STANDARDS AND SPECIFICATIONS APPROVED BY THE CITY OF TULSA, OKLAHOMA.
- 3.3. NO FENCE, WALL, BUILDING, OR OTHER OBSTRUCTION MAY BE PLACED OR MAINTAINED IN STORMWATER DETENTION EASEMENTS NOR SHALLTHERE BE ANY ALTERATION OF GRADE IN SAID EASEMENTS UNLESS APPROVED BY THE CITY OF TULSA, OKLAHOMA.
- 3.4. DETENTION, RETENTION, AND OTHER DRAINAGE FACILITIES SHALL BE MAINTAINED BY THE OWNER, TO THE EXTENT NECESSARY TO ACHIEVE THE INTENDED DRAINAGE, RETENTION, AND DETENTION FUNCTIONS INCLUDING REPAIR OF APPURTENANCES AND REMOVAL OF OBSTRUCTIONS AND SILTATION. DETENTION FACILITIES SHALL BE MAINTAINED BY THE OWNER IN ACCORDANCE WITH THE FOLLOWING MINIMUM STANDARDS:
- 3.4.1. GRASS AREAS SHALL BE MOWED (IN SEASON) AT REGULAR INTERVALS OF FOUR WEEKS, OR LESS.
- 3.4.2. CONCRETE APPURTENANCES SHALL BE MAINTAINED IN GOOD CONDITION AND REPLACED IF DAMAGED.
- 3.4.3. THE DETENTION EASEMENT SHALL BE KEPT FREE OF DEBRIS.
- 3.4.4. CLEANING OF SILTATION AND VEGETATION FROM CONCRETE CHANNELS SHALL BE PERFORMED TWICE YEARLY.
- 3.5. LANDSCAPING, APPROVED BY THE CITY OF TULSA, OKLAHOMA, SHALL BE ALLOWED WITHIN THE DETENTION EASEMENTS.
- 3.6. IN THE EVENT THE OWNER SHOULD FAIL TO PROPERLY MAINTAIN THE DETENTION, RETENTION, AND OTHER DRAINAGE FACILITIES OR, IN THE EVENT OF THE PLACEMENT OF AN OBSTRUCTION, OR THE ALTERATION OF GRADE WITHIN A DETENTION EASEMENT, THE CITY OF TULSA, OKLAHOMA, OR ITS DESIGNATED CONTRACTOR MAY ENTER AND PERFORM MAINTENANCE NECESSARY TO ACHIEVE THE INTENDED DRAINAGE AND DETENTION FUNCTIONS AND MAY REMOVE ANY OBSTRUCTION OR CORRECT ANY ALTERATION OF GRADE, AND THE COSTS THEREOF SHALL BE PAID BY THE OWNER. IN THE EVENT THE OWNER FAILS TO PAY THE COST OF MAINTENANCE AFTER COMPLETION OF THE MAINTENANCE AND RECEIPT OF A STATEMENT OF COSTS, THE CITY OF TULSA, OKLAHOMA, MAY FILE OF RECORD A COPY OF THE STATEMENT OF COSTS IN THE LAND RECORDS OF THE TULSA COUNTY CLERK, AND THEREAFTER THE COSTS SHALL BE A LIEN AGAINST THE PROPERTY IN THE SUBDIVISION. A LIEN ESTABLISHED AS ABOVE PROVIDED MAY BE FORECLOSED BY THE CITY OF TULSA, OKLAHOMA.

### 4. UTILITY SERVICE

4.1. OVERHEAD LINES FOR THE SUPPLY OF ELECTRIC, TELEPHONE AND CABLE TELEVISION SERVICES MAY BE LOCATED WITHIN THE PERIMETER EASEMENTS OF THE SUBDIVISION. STREET LIGHT POLES OR STANDARDS MAY BE SERVED BY OVERHEAD LINE OR UNDERGROUND CABLE, AND ELSEWHERE THROUGHOUT THE SUBDIVISION, ALL SUPPLY LINES INCLUDING ELECTRIC, TELEPHONE, CABLE TELEVISION AND GAS LINES SHALL BE LOCATED UNDERGROUND IN EASEMENTS DEDICATED FOR GENERAL UTILITY SERVICES AND IN THE RIGHTS-OF-WAY OF THE PUBLIC STREETS AS DEPICTED ON THE ACCOMPANYING PLAT. SERVICE PEDESTALS AND TRANSFORMERS, AS SOURCES OF SUPPLY AT SECONDARY VOLTAGES, MAY ALSO BE LOCATED

### IN GENERAL UTILITY EASEMENTS.

- UNDERGROUND SERVICE CABLES AND GAS SERVICE LINES TO ALL STRUCTURES WITHIN THE SUBDIVISION MAY BE EXTENDED FROM THE NEAREST GAS MAIN, SERVICE PEDESTAL OR TRANSFORMER TO THE POINT OF USAGE DETERMINED BY THE LOCATION AND CONSTRUCTION OF SUCH STRUCTURE UPON THE LOT, PROVIDED UPON INSTALLATION OF A SERVICE CABLE OR GAS SERVICE LINE TO A PARTICULAR STRUCTURE, THE SUPPLIER OF SERVICE SHALL THEREAFTER BE DEEMED TO HAVE A DEFINITIVE, PERMANENT, EFFECTIVE AND NON-EXCLUSIVE EASEMENT ON THE LOT, COVERING A 5 FOOT STRIP EXTENDING 2.5 FEET ON EACH SIDE OF THE SERVICE CABLE OR LINE EXTENDING FROM THE GAS MAIN, SERVICE PEDESTAL OR TRANSFORMER TO THE SERVICE ENTRANCE ON THE STRUCTURE.
- 4.3. THE SUPPLIER OF ELECTRIC, TELEPHONE, CABLE TELEVISION AND GAS SERVICE, THROUGH ITS AGENTS AND EMPLOYEES, SHALL AT ALL TIMES HAVE THE RIGHT OF ACCESS TO ALL UTILITY EASEMENTS SHOWN ON THE PLAT OR OTHERWISE PROVIDED FOR IN THIS DEED OF DEDICATION FOR THE PURPOSE OF INSTALLING, MAINTAINING, REMOVING OR REPLACING ANY PORTION OF THE UNDERGROUND ELECTRIC, TELEPHONE, CABLE TELEVISION OR GAS FACILITIES INSTALLED BY THE SUPPLIER OF THE UTILITY SERVICE.
- 4.4. THE OWNER OF ANY LOT SHALL BE RESPONSIBLE FOR THE PROTECTION OF THE UNDERGROUND SERVICE FACILITIES LOCATED ON THE OWNER'S LOT AND SHALL PREVENT THE ALTERATION OF GRADE OR ANY CONSTRUCTION ACTIVITY WHICH WOULD INTERFERE WITH THE ELECTRIC, TELEPHONE, CABLE TELEVISION OR GAS\_FACILITIES. EACH SUPPLIER OF THESE SERVICES SHALL BE RESPONSIBLE FOR ORDINARY MAINTENANCE OF UNDERGROUND FACILITIES, BUT THE LOT OWNER SHALL PAY FOR DAMAGE OR RELOCATION OF SUCH FACILITIES CAUSED OR NECESSITATED BY ACTS OF THE LOT OWNER OR THE LOT OWNER'S AGENTS OR CONTRACTORS.
- 4.5. THE COVENANTS SET FORTH IN THIS SUBSECTION SHALL BE ENFORCEABLE BY EACH SUPPLIER OF THE ELECTRIC, TELEPHONE, CABLE TELEVISION OR GAS SERVICE AND THE OWNER OF ANY LOT AGREES TO BE BOUND BY THESE COVENANTS.

### 5. WATER, SANITARY SEWER AND STORM SEWER SERVICES

- 5.1. THE OWNER OF ANY LOT SHALL BE RESPONSIBLE FOR THE PROTECTION OF THE PUBLIC WATER MAINS, SANITARY SEWER MAINS, AND STORM SEWERS LOCATED ON THE OWNER'S LOT.
- 5.2. WITHIN UTILITY EASEMENTS, RESTRICTED WATERLINE, SANITARY SEWER, STORM SEWER AND DRAINAGE EASEMENTS DEPICTED ON THE ACCOMPANYING PLAT, THE ALTERATION OF GRADE FROM THE CONTOURS EXISTING UPON THE COMPLETION OF THE INSTALLATION OF A PUBLIC WATER MAIN, SANITARY SEWER MAIN, OR STORM SEWER OR ANY CONSTRUCTION ACTIVITY WHICH, IN THE JUDGMENT OF THE CITY OF TULSA, WOULD INTERFERE WITH PUBLIC WATER MAINS, SANITARY SEWER MAINS, OR STORM SEWERS SHALL BE PROHIBITED.
- 5.3. THE CITY OF TULSA, OKLAHOMA, OR ITS SUCCESSORS, SHALL BE RESPONSIBLE FOR ORDINARY MAINTENANCE OF PUBLIC WATER SYSTEMS, SANITARY SEWER MAINS, AND STORM SEWERS BUT THE LOT OWNER SHALL PAY FOR DAMAGE OR RELOCATION OF SUCH FACILITIES CAUSED OR NECESSITATED BY ACTS OF THE LOT OWNER, OR THE LOT OWNER'S AGENTS AND/OR CONTRACTORS
- 5.4. THE CITY OF TULSA, OKLAHOMA, OR ITS SUCCESSORS, SHALL AT ALL TIMES HAVE RIGHT OF ACCESS TO ALL UTILITY EASEMENTS, RESTRICTED WATERLINE, SANITARY SEWER, STORM SEWER AND DRAINAGE EASEMENTS DEPICTED ON THE ACCOMPANYING PLAT, OR OTHERWISE PROVIDED FOR IN THIS DEED OF DEDICATION, FOR THE PURPOSE OF INSTALLING, MAINTAINING, REMOVING OR REPLACING ANY PORTION OF UNDERGROUND WATER, SANITARY SEWER, OR STORM SEWER FACILITIES.
- 5.5. THE COVENANTS SET FORTH IN THIS SUBSECTION SHALL BE ENFORCEABLE BY THE CITY OF TULSA, OKLAHOMA, OR ITS SUCCESSORS, AND THE OWNER OF EACH LOT AGREES TO BE BOUND BY THESE COVENANTS.

### 6. GAS SERVICE

- 6.1. THE SUPPLIER OF GAS SERVICE THROUGH ITS AGENTS AND EMPLOYEES SHALL AT ALL TIMES HAVE THE RIGHT OF ACCESS TO ALL UTILITY EASEMENTS SHOWN ON THE PLAT OR AS OTHERWISE PROVIDED FOR IN THIS DEED OF DEDICATION FOR THE PURPOSE OF INSTALLING, REMOVING, REPAIRING, OR REPLACING ANY PORTION OF THE FACILITIES INSTALLED BY THE SUPPLIER OF GAS SERVICE.
- 6.2. THE OWNER OF ANY LOT SHALL BE RESPONSIBLE FOR THE PROTECTION OF THE UNDERGROUND GAS FACILITIES LOCATED WITHIN THE LOT AND SHALL PREVENT THE ALTERATION OF GRADE OR ANY OTHER CONSTRUCTION ACTIVITY WHICH WOULD INTERFERE WITH GAS SERVICE. THE SUPPLIER OF GAS SERVICE SHALL BE RESPONSIBLE FOR THE ORDINARY MAINTENANCE OF ITS FACILITIES, BUT THE LOT OWNER SHALL PAY FOR DAMAGE OR RELOCATION OF FACILITIES CAUSED OR NECESSITATED BY ACTS OF THE LOT OWNER, OR THE LOT OWNER'S AGENTS OR CONTRACTORS.
- 3. THE COVENANTS SET FORTH IN THIS SUBSECTION SHALL BE ENFORCEABLE BY THE SUPPLIER OF THE GAS SERVICE AND THE OWNER OF THE LOT AGREES TO BE BOUND BY THESE COVENANTS.

### 7. LIMITS OF NO ACCESS

7.1. THE UNDERSIGNED OWNER/DEVELOPER HEREBY RELINQUISHES RIGHTS OF VEHICULAR INGRESS OR EGRESS FROM ANY PORTION OF THE PROPERTY ADJACENT TO SOUTH 103rd EAST AVENUE AND SOUTH 105th EAST AVENUE WITHIN THE BOUNDS DESIGNATED AS "LIMITS OF NO ACCESS" (L.N.A.) ON THE ACCOMPANYING PLAT, WHICH "LIMITS OF NO ACCESS" MAY BE AMENDED OR RELEASED BY THE TULSA METROPOLITAN AREA PLANNING COMMISSION, OR ITS SUCCESSOR, AND WITH THE APPROVAL OF THE CITY OF TULSA, OKLAHOMA, OR AS OTHERWISE PROVIDED BY THE STATUTES AND LAWS OF THE STATE OF OKLAHOMA PERTAINING THERETO, AND THE LIMITS OF NO ACCESS ABOVE ESTABLISHED SHALL BE ENFORCEABLE BY THE CITY OF TULSA.

### 8. PAVING AND LANDSCAPING WITHIN EASEMENTS

THE OWNER OF ANY LOT DEPICTED ON THE ACCOMPANYING PLAT SHALL BE RESPONSIBLE FOR THE REPAIR OF DAMAGE TO LANDSCAPING AND PAVING OCCASIONED BY INSTALLATION OR NECESSARY MAINTENANCE OF UNDERGROUND WATER, SANITARY SEWER, STORM SEWER, NATURAL GAS, COMMUNICATION, CABLE TELEVISION OR ELECTRIC FACILITIES WITHIN THE EASEMENT AREAS DEPICTED UPON THE ACCOMPANYING PLAT, PROVIDED THE CITY OF TULSA, OKLAHOMA, OR ITS SUCCESSORS, OR THE SUPPLIER OF THE UTILITY SERVICE SHALL USE REASONABLE CARE IN THE PERFORMANCE OF SUCH ACTIVITIES.

### 9. SIDEWALKS

9.1. SIDEWALKS TO BE TIED INTO EXISTING SIDEWALK ALONG SOUTH 105th EAST AVENUE IN ACCORDANCE WITH THE TULSA METROPOLITAN AREA SUBDIVISION AND DEVELOPMENT REGULATIONS. REQUIRED SIDEWALKS SHALL BE CONSTRUCTED AND MAINTAINED IN CONFORMANCE WITH THE CITY OF TULSA ENGINEERING DESIGN STANDARDS.

### 10. CERTIFICATE OF OCCUPANCY RESTRICTIONS

10.1. NO CERTIFICATE OF OCCUPANCY FOR A BUILDING WITHIN THE SUBDIVISION SHALL BE ISSUED BY THE CITY OF TULSA, OKLAHOMA UNTIL CONSTRUCTION OF THE REQUIRED INFRASTRUCTURE (STREETS, WATER, SANITARY SEWER, STORM SEWER SYSTEMS AND SIDEWALKS) SERVING THE ENTIRE SUBDIVISION HAS BEEN COMPLETED AND ACCEPTED BY THE CITY. NOTWITHSTANDING THE FOREGOING, THE CITY MAY AUTHORIZE THE ISSUANCE OF A TEMPORARY CERTIFICATE OF OCCUPANCY IF, IN THE CITY'S SOLE DISCRETION, THE CIRCUMSTANCES SUPPORT THE ISSUANCE. FURTHER NOTWITHSTANDING THE FOREGOING, THE CITY MAY AUTHORIZE THE PHASING OF THE CONSTRUCTION OF INFRASTRUCTURE WITHIN THE SUBDIVISION, AND IF PHASING IS AUTHORIZED, A CERTIFICATE OF OCCUPANCY FOR A BUILDING WITHIN AN AUTHORIZED PHASE MAY ISSUE UPON THE COMPLETION AND ACCEPTANCE OF THE INFRASTRUCTURE SERVING THE PARTICULAR PHASE. BUILDING CONSTRUCTION OCCURRING PRIOR TO THE CITY'S ACCEPTANCE OF THE INFRASTRUCTURE SHALL BE AT THE RISK OF THE OWNER OF THE LOT, NOTWITHSTANDING THE ISSUANCE OF A BUILDING PERMIT OR OF A TEMPORARY CERTIFICATE OF OCCUPANCY.

### SECTION II. ENFORCEMENT, DURATION, AMENDMENT AND SEVERABILITY

### 1. ENFORCEMENT

THE RESTRICTIONS HEREIN SET FORTH ARE COVENANTS TO RUN WITH THE LAND AND SHALL BE BINDING UPON THE OWNER/DEVELOPER, ITS SUCCESSORS AND ASSIGNS. WITHIN THE PROVISIONS OF SECTION I. STREETS, EASEMENTS AND UTILITIES ARE SET FORTH CERTAIN COVENANTS AND THE ENFORCEMENT RIGHTS PERTAINING THERETO, AND ADDITIONALLY THE COVENANTS WITHIN SECTION I, WHETHER OR NOT SPECIFICALLY THEREIN SO STATED, SHALL INURE TO THE BENEFIT OF AND SHALL BE ENFORCEABLE BY THE CITY OF TULSA, OKLAHOMA. IN ANY JUDICIAL ACTION BROUGHT TO ENFORCE THE COVENANTS ESTABLISHED WITHIN THIS DEED OF DEDICATION, THE DEFENSE THAT THE PARTY INITIATING THE EQUITABLE PROCEEDING HAS AN ADEQUATE REMEDY AT LAW IS HEREBY WAIVED

### 2. DURATION

THESE RESTRICTIONS AND COVENANTS, TO THE EXTENT PERMITTED BY APPLICABLE LAW, SHALL BE PERPETUAL BUT IN ANY EVENT SHALL BE IN FORCE AND EFFECT FOR A TERM OF NOT LESS THAN THIRTY (30) YEARS FROM THE DATE OF THE RECORDING OF THIS DEED OF DEDICATION UNLESS TERMINATED OR AMENDED AS HEREINAFTER PROVIDED.

### 3. AMENDMENT

THE COVENANTS CONTAINED WITHIN SECTION I. STREETS, EASEMENTS AND UTILITIES MAY BE AMENDED OR TERMINATED AT ANY TIME BY A WRITTEN INSTRUMENT SIGNED AND ACKNOWLEDGED BY THE OWNER OF THE LAND TO WHICH THE AMENDMENT OR TERMINATION IS TO BE APPLICABLE AND APPROVED BY THE TULSA METROPOLITAN AREA PLANNING COMMISSION, OR ITS SUCCESSORS AND THE CITY OF TULSA, OKLAHOMA. THE PROVISIONS OF ANY INSTRUMENT AMENDING OR TERMINATING COVENANTS AS ABOVE SET FORTH SHALL BE EFFECTIVE FROM AND AFTER THE DATE IT IS PROPERLY RECORDED IN THE RECORDS OF THE COUNTY CLERK OF TULSA COUNTY.

### 4. SEVERABILITY

INVALIDATION OF ANY RESTRICTION SET FORTH HEREIN, OR ANY PART THEREOF, BY AN ORDER, JUDGMENT, OR DECREE OF ANY COURT, OR OTHERWISE, SHALL NOT INVALIDATE OR AFFECT ANY OF THE OTHER RESTRICTIONS OR ANY PART THEREOF AS SET FORTH HEREIN, WHICH SHALL REMAIN IN FULL FORCE AND EFFECT.

### 

GIVEN UNDER MY HAND AND SEAL OF OFFICE THE DAY AND YEAR LAST ABOVE WRITTEN.

### **CERTIFICATE OF SURVEY**

OKLAHOMA NO. 1815

MY COMMISSION EXPIRES:

I, CLIFF BENNETT, A REGISTERED LAND SURVEYOR IN THE STATE OF OKLAHOMA, HEREBY CERTIFY THAT I HAVE CAREFULLY AND ACCURATELY SURVEYED, SUBDIVIDED AND PLATTED THE TRACT OF LAND DESCRIBED ABOVE, AND THAT SAID PLAT DESIGNATED HEREIN AS THE FINAL PLAT OF "JACK WILLS", A SUBDIVISION IN THE CITY OF TULSA, TULSA COUNTY, STATE OF OKLAHOMA, IS A TRUE AND CORRECT REPRESENTATION OF SAID SURVEY.

**NOTARY PUBLIC** 

WITNESS MY HAND AND SEAL T	HIS	_DAY OF	, 2023.
CLIFF BENNETT			
REGISTERED PROFESSIONAL L	AND SURVEYOR	3	


STATE OF OKL	_AHOMA )				
COUNTY OF _	)				
BEFORE ME,	THE UNDERSIGNED,	A NOTARY PUBLIC IN	N AND FOR SAID C	OUNTY AND STA	TE, ON TH
[	DAY OF	, 2023., PERSONALLY	APPEARED CLIFF	BENNETT TO ME	KNOWN T

\_\_\_\_\_DAY OF \_\_\_\_\_, 2023., PERSONALLY APPEARED CLIFF BENNETT TO ME KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT.

GIVEN UNDER MY HAND AND SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.

MY COMMISSION EXPIRES:	
	NOTARY PUBLIC

PROJECT JACK WILLS
PRELIMINARY PLAT - AUGUST 07, 2023
Sheet 2 of 2



SAFETY FENCE SHALL BE INCLUDED IN OTHER PAY ITEMS.

THROUGHOUT THE PROJECT.

29. ALL UNSUITABLE MATERIALS REMOVED DURING TRENCHING OR EXCAVATION SHALL

BE DISPOSED OF AT A SITE APPROVED BY THE OWNER AND ENGINEER. PRIOR TO

DISPOSAL SITE TO THE OWNER AND ENGINEER FOR THEIR REVIEW. MAINTENANCE OF

STOCKPILE SITES IS THE SOLE RESPONSIBILITY OF THE CONTRACTOR. CONTRACTOR

TRENCHING OR EXCAVATION, THE CONTRACTOR SHALL SUBMIT THE PROPOSED

MUST MAINTAIN STOCKPILE SITES IN A SAFE, POLLUTION FREE CONDITION

19. DURING CONSTRUCTION, TEMPORARY PLUGS SHALL BE INSTALLED AT ALL OPENINGS

21. WATER LINES SHALL BE INSTALLED PER LOCAL AUTHORITIES HAVING JURISDICTION

ALL TIMES TO ROADWAYS, DRIVEWAYS AND BUILDING ENTRANCES.

WHENEVER ANY PIPELINE IS LEFT UNATTENDED.

OR AS SPECIFIED ON PLANS.

11. ALL MATERIALS, CONSTRUCTION AND INSPECTION FOR WATER AND SANITARY SEWER 20. ADEQUATE EMERGENCY VEHICLE AND PEDESTRIAN ACCESS SHALL BE MAINTAINED AT

FEDERAL OSHA REGULATIONS.

10. REFER TO BUILDING PLANS FOR SITE LIGHTING ELECTRICAL PLAN.

12. THE CONTRACTOR SHALL COORDINATE WATERMAIN WORK WITH THE FIRE

DEPARTMENT AND THE CITY UTILITY DEPARTMENT TO PLAN PROPOSED

IMPROVEMENTS AND TO ENSURE ADEQUATE FIRE PROTECTION IS CONSTANTLY


LINES SHALL BE PER CITY STANDARD SPECIFICATION.

!! WARNING TO CONTRACTOR!

EXISTING UTILITIES AND UNDERGROUND FACILITIES INDICATED ON THESE PLANS HAVE BEEN LOCATED BY USING AVAILABLE INFORMATION FROM UTILITY LOCATION SERVICES (OKIE), MAPS. AS-BUILTS AND ON-SITE PERSONNEL. THEIR LOCATION AND EXISTENCE IS NOT TO BE CONSIDERED ACCURATE OR COMPLETE. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO VERIFY THE EXISTENCE ALONG WITH THE HORIZONTAL AND VERTICAL LOCATION OF ALL EXISTING UTILITIES AND UNDERGROUND FACILITIES PRIOR TO CONSTRUCTION. THE CONTRACTOR IS TO PRESERVE AND PROTECT ANY AND ALL EXISTING UTILITIES THAT ARE TO REMAIN FROM DAMAGE DURING

THIS DOCUMENT IS PRELIMINARY IN NATURE AND IS NOT A FINAL, SIGNED AND SEALED DOCUMENT


BILLY COX, P.E. ROUTE 66 ENGINEERING, LLC



CA #8853, DATE 06/30/2025

SCALE: 1" = 30'





## **コ**の



6" (SCH-40) PVC, FIRE WATER SERVICE FROM METER INSTALLED PER STATE AND LOCAL REGULATION. CONTRACTOR RESPONSIBLE FOR

POINT OF CONNECTION FOR SANITARY SEWER SERVICE. VERIFY FLOW LINE, IF NECESSARY ADJUST SLOPE AND FLOW LINES TO ACCOMMODATE ACTUAL TIE IN ELEVATION. TIE IN THE PROPOSED

 $\langle$  I angle GREASE INTERCEPTOR. REFER TO PLUMBING PLANS FOR DETAILS.

THREE (3) 75KVA POLE MOUNTED ELECTRICAL TRANSFORMERS AND PRIMARY ELECTRIC LINE. CONTRACTOR SHALL COORDINATE AND VERIFY POINT OF CONNECTION FOR ELECTRICAL LINES. CONNECTION SHALL BE MADE PER LOCAL AND STATE REGULATIONS.

UNDERGROUND SECONDARY ELECTRIC LINE. CONTRACTOR TO

GAS METER AND GAS LINE FROM METER TO GAS MAIN. CONTRACTOR SHALL COORDINATE WITH THE UTILITY PROVIDER TO VERIFY POINT OF CONNECTION, PROVIDE TRENCHING, ENCASEMENT, EQUIPMENT PADS, METER LOCATION AND BACKFILL AS REQUIRED.

TELEPHONE LINE. CONTRACTOR SHALL COORDINATE WITH SERVICE PROVIDER INSTALLATION AND VERIFY POINT OF CONNECTION.

FIRE DEPARTMENT CONNECTION. REFER TO PLUMBING PLANS FOR **DETAILS** 


CONTRACTOR TO VERIFY UTILITY BUILDING PENETRATIONS WITH PLUMBING AND ELECTRICAL PLANS.

WILI h E. AVI

??/??/2023


APPV. BY

**CU101** 




THIS DOCUMENT IS
PRELIMINARY
IN NATURE AND IS NOT
A FINAL, SIGNED AND
SEALED DOCUMENT

BILLY COX, P.E. ROUTE 66 ENGINEERING, LLC CA #8853, DATE 06/30/2025



SCALE: 1" = 30'





route 66 engineering



K WILLS

105th E. AVENUE

DKI AHOMA 74133

PLAN

SIT


JACK V 6414 S. 105th I TULSA, OKLAH

DRAWN BY: JD

APPV. BY: BC

DATE: ??/??/2023

\_ CS101



- PLANS AND SPECIFICATIONS.
- 3. THE MAXIMUM CROSS SLOPE ON ANY SIDEWALK OR RAMP SHALL BE TWO PERCENT.
- 4. EQUIPMENT AND MATERIALS SHALL BE INSTALLED IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS AND SPECIFICATIONS.
- 5. UNLESS OTHERWISE SHOWN, NEW PAVING SHALL BE CONSTRUCTED TO ALLOW FOR POSITIVE DRAINAGE TO CATCH BASIN, CURB, GUTTER, AND OTHER RUNOFF COLLECTION DEVICES. NEW PAVEMENT SLOPE SHALL BE MINIMUM 0.50% FOR CONCRETE AND 1.5% FOR ASPHALT UNLESS OTHERWISE INDICATED OR DIRECTED BY THE ARCHITECT/ENGINEER.
- ALL DISTURBED AREAS THAT ARE NOT TO BE PAVED SHALL BE SODDED UNLESS NOTED OTHERWISE. ENSURE ALL DISTURBED AREAS HAVE TOPSOIL TO A DEPTH OF FOUR TO SIX INCHES (4"-6").
- THE CONTRACTOR SHALL KEEP THE SITE CLEAN AT ALL TIMES AND CONTROL DUST RESULTING FROM THE EARTHWORK OPERATIONS. THE CONTRACTOR SHALL NOT TRACK MUD ON THE PUBLIC STREETS.
- NEW CONTOURS DENOTE TOP OF FINISHED PAVING AND GRADED AREA AS INDICATED. ALL PROPOSED ELEVATIONS ARE TOP OF CURB, GUTTER OR FINISH GRADE AS INDICATED ON THE PLANS, UNLESS NOTED OTHERWISE.
- PUBLIC STORM DRAIN SYSTEMS AND STRUCTURES SHALL BE CONSTRUCTED IN ACCORDANCE WITH COUNTY/CITY STANDARD DRAWINGS AND SPECIFICATIONS.
- 10. THE CONTRACTOR SHALL PROTECT EXISTING UTILITIES AND SHALL NOT DAMAGE OR DISTURB ANY SERVICE. THE CONTRACTOR SHALL REPAIR, AT CONTRACTOR'S OWN EXPENSE, ANY DAMAGED UTILITIES CAUSED BY CONSTRUCTION 20. ALL STORM SEWER MANHOLES IN PAVED AREAS SHALL BE FLUSH WITH THE PAVEMENT AND SHALL HAVE TRAFFIC OPERATIONS.

- 12. ADJUST ALL VALVE BOXES AND MANHOLE COVERS TO FINISHED GRADE WHEN APPLICABLE.
- 13. IF FIELD GRADE ADJUSTMENTS ARE REQUIRED, THE CONTRACTOR SHALL NOTIFY THE ENGINEER.
- 14. MANHOLE LIDS AND SLEEVES IN PAVED AREAS SHALL BE HS-25 TRAFFIC RATED.
- 15. IF, AT ANY TIME THE CONTRACTOR FINDS ERROR AND/OR CONFLICTS IN THE CONTRACT DOCUMENTS, THE CONTRACTOR SHALL NOTIFY THE ARCHITECT/ENGINEER FOR CLARIFICATION PRIOR TO CONSTRUCTION.
- CONTRACTOR SHALL FIELD VERIFY ALL DIMENSIONS AND ELEVATIONS. ANY DISCREPANCY FOUND SHALL BE DISCUSSED WITH THE ENGINEER OF RECORD PRIOR TO ANY CONSTRUCTION WORK
- 17. THE LOCATION AND/OR ELEVATION OF EXISTING UTILITIES AS SHOWN ON THESE PLANS IS BASED ON RECORDS OF THE 25. IF ANY EXISTING STRUCTURES TO REMAIN ARE DAMAGED DURING CONSTRUCTION, IT IS THE CONTRACTOR'S VARIOUS UTILITY COMPANIES, AND WHERE POSSIBLE, MEASUREMENTS TAKEN IN THE FIELD. THE INFORMATION IS NOT TO BE RELIED ON AS BEING EXACT OR COMPLETE. THE CONTRACTOR MUST CONTACT THE APPROPRIATE UTILITY COMPANIES AT LEAST 72 HOURS BEFORE ANY EXCAVATION TO REQUEST EXACT FIELD LOCATION OF EXISTING UTILITIES ON SITE OR IN RIGHT-OF-WAY. ALL UTILITIES MUST BE LOCATED PRIOR TO GRADING START.
- 18. ALL CUT OR FILL SLOPES SHALL BE A MAX 3:1 SLOPE OR FLATTER UNLESS OTHERWISE NOTED.
- 19. ALL STORM SEWER PIPE CONNECTIONS TO STRUCTURES SHALL BE GROUTED TO ASSURE CONNECTION AT STRUCTURE IS WATERTIGHT. ALL STORM SEWER STRUCTURES SHALL HAVE A SMOOTH UNIFORM POURED MORTAR INVERT FROM INVERT IN TO INVERT OUT.
- BEARING RINGS AND COVERS. MANHOLES IN UNPAVED AREAS SHALL BE 3" ABOVE FINISH GRADE. LIDS SHALL BE

- 21. SITE GRADING SHALL NOT PROCEED UNTIL APPROPRIATE EROSION AND SEDIMENT CONTROL MEASURES HAVE BEEN INSTALLED. THE CONTRACTOR SHALL ADHERE TO ALL TERMS AND CONDITIONS AND OUTLINED IN THE GENERAL NPDES PERMIT AND THE SWPPP FOR STORMWATER DISCHARGE ASSOCIATED WITH CONSTRUCTION ACTIVITIES.
- 22. ALL UNSURFACED AREAS DISTURBED BY GRADING OPERATION SHALL RECEIVE FOUR TO SIX INCHES (4"-6") OF TOPSOIL TO FINAL GRADE. REFER TO THE LANDSCAPE PLAN.
- 23. THE CONTRACTOR SHALL ASSURE POSITIVE DRAINAGE AWAY FROM BUILDINGS FOR ALL NATURAL AND PAVED AREAS THROUGHOUT ALL PHASES OF CONSTRUCTION.
- 24. CONTRACTOR SHALL REFER TO ARCHITECTURAL PLANS FOR EXACT LOCATIONS AND DIMENSIONS OF VESTIBULES. SLOPE PAVING, SIDEWALKS, EXIT PORCHES, TRUCK DOCKS, PRECISE BUILDING DIMENSIONS AND EXACT UTILITY **ENTRANCE LOCATIONS.**
- RESPONSIBILITY TO REPAIR AND/OR REPLACE THE EXISTING STRUCTURE, AS NECESSARY, TO RETURN IT TO THE EXISTING CONDITION OR BETTER. CONTRACTOR SHALL REPAIR AND RESTORE ANY AREAS DAMAGED DURING
- 26. NO HAZARDOUS MATERIALS SHALL BE BROUGHT ON SITE OR GENERATED AT THE SITE.

CONSTRUCTION AS HIS OWN EXPENSE.

27. FOLLOW ALL RECOMMENDATIONS IN GEOTECHNICAL REPORT BY AIMRIGHT & TESTING AND ENGINEERING, LLC DATED AUGUST 24, 2021. IF CONTRACTOR DISCOVERS UNFORESEEN SOIL CONDITIONS PLEASE CONTACT ENGINEER IMMEDIATELY.


THIS DOCUMENT IS PRELIMINARY IN NATURE AND IS NOT A FINAL, SIGNED AND SEALED DOCUMENT

BILLY COX, P.E.

ROUTE 66 ENGINEERING, LLC CA #8853, DATE 06/30/2025

SCALE: 1" = 30'





30 <u>0</u>€



WIL h E. AV GRADIN

APPV. BY

**CG101**